

CASE STUDY

PURE GYM, Southampton

The award winning Pure Gym brand required a waterproofing solution for their latest development.



THE CHALLENGE

The Pure Gym concept is based around the passion for fitness. Pure Gym provide functional training zones for their members, open 24/7, any day or night, with state of the art fitness equipment and no need for a membership contract.

Pure Gym contacted Wetrooms UK to manufacture and install level entry drainage and waterproofing systems into

the male and female shower cubicles in their new gym development at Southampton.

The two shower blocks needed to be fully waterproofed and appropriate drainage systems installed capable of coping with flow rates of up to 24 litres per minute, prior to the installation of six shower cubicles per block.



THE SOLUTION

Wetrooms UK recommended the specification of Six Modular Wet-floor Systems for installation on the timber floor. The six floor formers were butted together and installed side by side, creating individual falls towards the contemporary linear drains. In addition, floor formers were installed alongside the cubicles resulting in the whole shower area being laid to fall.

Six vertical drainage traps and slotted stainless steel grills capable of coping with constant flow rates of up to 24 litres per minute were installed in the floor, prior to waterproofing and the application of floor and wall tiles.

RIW Tilesafe waterproof membrane was applied to the floor and wall junctions within the shower areas and across the entire floor area. RIW Flexible Wall Membrane was applied full height to the shower walls, linking to the RIW Tilesafe membrane, to prevent any water penetration.



CLIENT TESTIMONIAL:

"We invited Wetrooms UK to waterproof and install drainage systems within the wet areas of the new Pure Gym at Southampton. We were delighted with the outcome and the new shower blocks have been well received by our members. Wetrooms UK have been a pleasure to work with on the Southampton project and numerous other Pure Gym sites. They have been approachable and helpful and nothing has been a problem for them."

John Graham, Snr Project Manager, Pure Gym

PRODUCTS SPECIFIED

Modular Wet-floor Systems
(1200 x 1200 tapered boards)

800mm Slotted Linear Drains

RIW Tilesafe Kits

RIW Flexible Wall Membrane